



Water Environment Association
Preserving & Enhancing Ohio's Water Environment



2011 OWEA Annual Conference
June 22, 2011

When Disaster Strikes

Dan Miklos, Senior Associate, Midwest Region



HAZEN AND SAWYER
Environmental Engineers & Scientists


Agenda

- The Flood of 2010
 - Disaster provides an opportunity to re-think earlier decisions
 - Correcting long term design problems
 - Dewatering, Biosolids Processing and Disposal are changed
- Existing Sludge Processing and Disposal
 - Sludge Conditioning and High Pressure Pumping.
 - Plate and Frame Presses with Drag Chain Conveyance to RDP Class A Processing
 - RDP Processing to Class A Biosolids
- Current full scale pilot testing
 - Centrifuge
 - Belt Press
- Low technology solutions for long term disposal.

The Clarksville Flood of 2010

- Characterized as “far greater” than a 1,000 year rain event - 36 hours of rain totaled 17 inches on May 1 and May 2, 2010. 26 fatalities on May 2, 2010.
- BP Deepwater Horizon Oil Rig explosion and oil spill on April 20, 2010 kept the nation’s attention.
- The Army Corps of Engineers released 1.4B gallons of water in 1 hour to save upstream dams.
- The Clarksville WWTP was flooded and remained under water for approximately 6 days.
- Severe damage with prolonged submergence as opposed to a storm surge that quickly recedes. Every cable and conductor had to be removed.

Weekend Rainfall Totals - May 1st & 2nd, 2010 Tennessee



Source: CoCoRaHS


0 25 50 100 150
Miles

Precipitation Contours

| In Inches | |
|---------------|-----------------|
| 0.01" - 2.00" | 8.01" - 10.00" |
| 2.01" - 4.00" | 10.01" - 12.00" |
| 4.01" - 6.00" | 12.01" - 14.00" |
| 6.01" - 8.00" | 14.01" - 16.00" |
| | 16.01" - 20.00" |

This map is an interpolation of actual reported values,
but should be considered an estimation only.

Created by the National Weather Service Forecast
Offices Nashville, Tennessee & Louisville, Kentucky



City of Clarksville, TN

1,000 Year Flood Recovery Team

- Hazen and Sawyer, Project Management
- Allied Technical Services, Sharonville, OH, Site Dewatering, Underwater Services, Equipment repair/replacement
- MSD Equipment, Centerville, OH, Sludge Dewatering
- Shermco Industries, Dallas Texas, Electrical Contracting
 - Aggreko: Generators, dehumidification, air handling
 - Belfor: Property restoration/cleaning

Clarksville, TN: May 1, 2010, Cumberland and Red River Confluence



Flood Breach-North Levy

5/3/2010



Low Point-South End of Plant

5/3/2010



Site Drainage To Plants Stormwater Pump Station 5/3/2010



Stormwater Pump Station


Too Much Flow!

5/3/2010



Initial Recovery Timeline

- Event: **May 1-2**
- WWTP Site Flooded: **May 3**
- River Crest: **May 4**
- Emergency response contractor hired (pumps, generators, manpower, electrician, etc.): **May 4**
- Site dewatered: **May 5-9**
- Primary Treatment restored: **May 12**
- Electrical Contractor Selected: **May 14**
- Temporary dewatering company selected: **May 15**
- Electrical contractor began work: **May 15**
- Site cleaning and disinfection contractor began work: **May 16**
- Temporary solids dewatering belt press on-site: **May 21**



NPDES Permit...Water Quality!

- Immediate communication with TDEC HQ and field office
- Daily written report to TDEC concerning flood recovery progress
- All floodwater from site disinfected and pumped through GeoTube
- All wastewater effluent disinfected prior to discharge (bulk hypochlorite)
- Primary Treatment: Wednesday, May 12 (3 days after site dewatered)
- Secondary Treatment: August (over 3 months after site dewatering complete) Turblex blowers, air system, diffusers, AB tanks, power, etc...

Deep Thoughts...FEMA

- Waterline matters...
- Keep lines of communication open.
- Define “emergency condition” and purchasing requirements associated with the emergency.
- But...the story can change...get it in writing
- Define Project Worksheet “projects” early.
- Don’t build in a COE flowage easement.
- Levee?
- More to come.

Clarksville, TN: Clarksville WWTP Following Levee Breach



Clarksville WWTP: Solids Handling Facility



Administration Building Roof Lifted

Tuesday 5/4/2010



Administration Building

Wednesday 5/5/2010





Clarksville WWTP:
Solids Handling Facility
May 6, 2010

Clarksville WWTP:
Solids Handling Facility
May 7, 2010





Clarksville WWTP:
Solids Handling Facility
May 8, 2010

Clarksville WWTP:
Solids Handling Facility
May 9, 2010



Administration Building

Saturday 5/8/2010



Flood Recovery Begins

All Site Dewatering to GeoTube Silt Bags





Allied Technical
Underwater Services
Primary Settling



Refrigerators Can Float

5/9/2010



Aeration Tanks Area Dewatering

5/7/2010



Sludge Conditioning Building

“Mud” and “Sludge”

5/12/2010



Site Dewatering

5/8/2010



Clari-Vac Systems In Secondary Clarifiers Floated Out of Tanks 5/9/2010



Clari-Vac Systems Floated Out of Tanks 5/18/2010



RECOVERY... a daunting task!



Flood Recovery Begins: Competing for Resources

Temp. Generators and Pumps Arrive

5/7/2010



Flood Recovery Begins Generators and Dehumidifiers Arrive 5/15/2010



Cleaning Crews Mobilize

5/16/2010



Building Interiors Vacuumed

5/27/2010



Temporary Belt Press

5/27/2010



125 Contractors On-site: Daily coordination changes! Cleaning, Mech. & Elec. Repairs 5/27/2010



All Electrical Wire Removed and Salvaged 6/18/2010



Clari-Vac Systems Repaired

7/28/2010



New Clari-Vac LCP's

7/29/2010



Turblex Blowers Refurbished New LCPs. Motors Rewound 7/29/2010



Aeration Basins

Diffuser Replacement Tank No. 1

8/2/2010



Belt Thickener Building

Ashbrook GBT's Refurbished

8/3/2010



Belt Thickener Building

Ashbrook GBT's Refurbished

8/21/2010



Temporary Mobile Substation

8/21/2010



Effluent Pump Station

New VFD's for 5 Effluent Pumps

8/21/2010



May 5, 2011



Secondary Settling Tanks 5 through 9 Commissioning Completed 8/30/2010



Aeration Basins

Diffuser Replacement Tank No. 1 Complete

8/31/2010



New MCC Primary Sludge Building 10/28/2010



New MCC
Belt Thickener Building
2/18/2011



Clarksville Solids Processing

- Three (3) Structures / Processes:
 - Sludge Conditioning and High Pressure Pumping.
 - Plate and Frame Presses with Drag Chain Conveyance to RDP Class A Processing
 - RDP Processing to Class A Biosolids
- Hazen and Sawyer recommended the City reconsider their sludge processing selection. The flood enabled the City to evaluate earlier decisions regarding capital investment in dewatering and Class A Processing.
- FEMA and flood insurance enabled the City to provide for re-investment with a change in technology approach.

Sludge Conditioning



Plate and Frame Presses



Drag Chain Conveyors



Pug Mill Operation with Post Lime Treatment for Class A Processing



Long Sweep Conveyors for Loading Station



Loading Station



Existing Sludge Processing Equipment: connected hp

| | connected hp | Number | total hp |
|--------------------------|--------------|-----------------|--------------|
| Grinder Pumps | 3 | 2 | 6 |
| Mixer Pit | 1.5 | 1 | 1.5 |
| Odor control | 2 | 2 | 4 |
| Lime feed tank mixer | 15 | 1 | 15 |
| Silo screw conveyor | 5 | 1 | 5 |
| Transfer screw conveyor | 5 | 1 | 5 |
| Lime Hose Pump | 10 | 3 | 30 |
| Ferric Pump | 2 | 1 | 2 |
| RDP Sludge Storage Mixer | 1 | 2 | 2 |
| Press Feed Pumps | 25 | 5 | 125 |
| Air Compressor | 30 | 2 | 60 |
| Drag chain conveyor | 25 | 5 | 125 |
| Transfer Screws | 25 | 5 | 125 |
| Sludge Lime Mixers | 25 | 3 | 75 |
| Pug mill | 25 | 3 | 75 |
| Cross Belt Plow | 15 | 2 | 30 |
| Cross Conveyors | 5 | 2 | 10 |
| Intermediate Conveyor | 5 | 2 | 10 |
| Shuttle Conveyor | 2 | 2 | 4 |
| Shuttle Trolley | 2 | 2 | 4 |
| Vibrator | 1.32 | 3 | 3.96 |
| Long sweep conveyor | 25 | 2 | <u>50</u> |
| | | total hp | 767.5 |

Sludge Processing Operating Costs:

Power:

| | |
|-------------------------|-----------------------|
| total hp hrs | 37,323 |
| hp/kw | 1.34 |
| \$/kwhr | \$0.08 |
| total power cost | \$2,152\$/week |

Chemistry:

| Lime Feed | Pressings/wk | lbs/pressing | |
|-----------------------------------|---------------|--------------------|------------------------------|
| Lime Feed (1,000 lbs for Press) | 51 | 1,000 | 51,000 <i>lb/week</i> |
| Lime Feed (1,200 lbs for Class A) | 51 | 1,200 | <u>61,200</u> <i>lb/week</i> |
| | | total lime | 112,200 <i>lb/week</i> |
| | Lime Cost/ton | | <u>\$168</u> \$/ton |
| | | lime cost | \$9,425\$/week |
| Ferric Chloride (100 gals/press') | 51 | 100 | 5,100 <i>gallons</i> |
| Ferric Chloride Cost/lb | | | \$0.127 |
| Ferric Chloride Specific Gravity | | | <u>1.41</u> |
| | | ferric cost | \$7,617\$/week |

Sludge Processing Operating Costs:

Labor:

| | |
|-----------------------------------|--|
| Operating hours/week for staffing | 55 hrs |
| Press Room Operators | 2 |
| Control Room Operator (Pug mill) | 1 |
| Truck and Front Loader | 0.5 |
| | 192.5 manhours/wk |
| | \$15.50 hourly rate |
| | 1.42 benefits rate |
| | total labor cost \$4,237 \$/week |

Maintenance and Disposal Costs: **\$2,000 \$/week**

- Significant annual costs:
 - Drag chain conveyors at \$140,000 per unit. One unit under repair when work stopped due to flood.
 - New plate and frame press @ \$1.3M installed
 - Chemical feed, smaller conveyance systems, high pressure pumping all contributed to significant maintenance costs.
 - City was required to haul solids land application sites.

Sludge Conditioning Building

Temporary piping/grinders and flow metering



**Pug Mill Building
Long Sweep Conveyors and
Loading Station Removed**



**Frac Tank Blending
Flottweg Centrifuge
BDP Belt Press**



BDP 3 Belt Press MSD Equipment



Pug Mill Building



30 cyd Roll Off – BP and Centrifuge Loading



Future Sludge Processing Equipment: connected hp

| Two Presses | connected hp | Number | total hp |
|--------------------|-------------------------|---------------|---------------------|
| Drive | 5 | 2 | 10 |
| Wash water | 15 | 2 | 30 |
| Gravity Section | 2 | 2 | 4 |
| Feedbox | 0.5 | 2 | 1 |
| Hydraulic System | 3 | 2 | 6 |
| Feed pump | 20 | 2 | <u>40</u> |
| | | total hp | 91 |

Projected Sludge Processing Operating Costs:

Power:

| | |
|--------------|---------------------|
| total hrs/wk | 66 |
| total hp hrs | 6,006 |
| hp/kw | 1.34 |
| \$/kwhr | \$0.08 |
| total power | \$346\$/week |

Chemistry:

| | |
|--------------------------------------|-----------------------|
| emulsion polymer cost | \$0.90/lb |
| activity | 0.36 |
| assume 7 lbs active polymer / dt | 7lbs/dry ton |
| * high charge, high wt, large branch | |
| Polymer usage / dry ton | \$17.50 cost/dry ton |
| emulsion polymer cost/day | \$329.50 cost/day |
| Polymer cost | \$1,648\$/week |

Projected Sludge Processing Operating Costs:

Labor:

| | |
|----------------------|-----------------------|
| Press Room Operators | 1 |
| Operator for Loading | 0.5 |
| | 99manhours/wk |
| | \$15.50hourly rate |
| | 1.42benefits rate |
| Total labor | \$2,179\$/week |

Maintenance and Transportation Costs:

- Significant annual costs:
 - Example is landfill transportation and tipping fee (next slide)
 - In comparison, minimal maintenance anticipated.
 - Class B land application would require future land acquisition and cake storage for fecal reduction.

Projected Sludge Processing Operating Costs:

Projected Cost of Operation (landfill disposal)@ 9.5 MGD

| | | |
|---|----------------|-----------------|
| Dumpster Charge (tipping and transportation) | \$194.40 | 30 cyd dumpster |
| Projected primary and waste sludge cake | 22.0% | |
| Projected dry lbs (primary & secondary) | 37,657 | dry lbs/day |
| Projected wet lbs (primary & secondary) cake | 171,170 | wet lbs/day |
| Cake solids weight/cf | 60 | lbs/cf |
| Projected Wet Volume to disposal | 2,853 | cf/day |
| Projected Wet Volume to disposal dumpster volume | 106 | cyd/day |
| dumpsters/day | 30 | cy |
| disposal cost at landfill | 3.5 | |
| | \$3,243 | \$/week |

Projected Sludge Processing Operating Costs:

Plate and Frame/Class A versus Belt Press/Class B

| | P&F/Class A | BP/Class B |
|--------------------------|--------------------|------------------|
| Dewatering | | |
| Power | \$2,152 | \$346 |
| Chemistry | \$17,041 | \$1,648 |
| Labor | \$4,237 | \$2,179 |
| Maintenance/Disposal | <u>\$2,000</u> | <u>\$3,423</u> |
| <i>total weekly cost</i> | \$25,430 | \$7,596 |
| <i>total annual cost</i> | \$1,322,360 | \$394,992 |

Considerations for the Future:

1. Do not underestimate capital equipment decisions and the momentum or direction that provides to a utility.
 - Capital investment reduces options as capitalization and the resulting debt service leaves less room in the budget. The City of Clarksville is not comfortable further impact debt service and limit future options by remaining a “Class A processing facility”.
2. The first decision: abandon plate and frame presses:
 - Two (2) dewatering methods are being considered: Belt Press and Centrifuge. Full scale pilot units are being tested.
 - Flottweg Z5E with a 20.8 inch bowl
 - BDP – 1 meter – 3 belt
 - Lime addition for dewatering is **not** an option:

Drain Pump Station Discharge Header



Considerations for the Future:

3. Re-tool for long term biosolids disposal. Key issues for a successful venture: (con't)
 1. Site is land locked within the levee. Biosolids processing would limit the site for additional wet stream treatment.
 2. Sludge storage and processing must be located off-site. The City is committed to eliminating long standing odor problems at the facility with new upgrades throughout the facility.
 3. Minimize capital investment at the site to maintain “debt service options” off site. Class A capitalization showed no return on investment (ROI).
 4. Develop a more efficient and cost effective dewatering option as a starting point for long term disposal options. Further solids stabilization at the facility would occupy limited wet stream processing area and complicate an odor sensitive facility.

Considerations for the Future:

4. Evaluate the paradigm shift in the organization. Biosolids disposal commitment can range from:
 - minimal staff investment/commitment – landfill cake solids without further processing.
 - Increase staff investment/commitment by increasing material handling capability to achieve a more cost effective disposal option. Consider low technology / low capital alternatives:
 - Remote sludge storage for Class B compliance and land application
 - Remote sludge storage for cost effective access to area farms
 - Invest in farm purchase to incorporate disposal and crop rotation with surrounding farms.
 - Minimize sludge volume and handling requirements. Class A processing showed little return on investment. Class A processing averaged approximately 45% of the total disposal requirement.

Considerations for the Future:

5. “Class A” versus “Class B” is one of the few times that the selection and process design are based on factors that are outside the fence.
 - Beneficial use of biosolids is our goal, but the City has a responsibility to the rate payers to minimize cost.
 - Class A versus Class B needs to be a team decision with client ownership – it is not the design engineer’s decision.
 - Effective dewatering is critical to any downstream processing. Optimize not only the dewatering process/equipment but also solids conditioning (or plan to eliminate it).
 - There is no right or wrong answer, but the successful decision must have ownership throughout the Utility

Operations staff return to normal duties



Questions???

