

Columbus Collection and Treatment System Real Time Wet Weather Operational Implementation


Presenters

Ed Heyob, CDM Smith Automation Engineer

Kim Brown, JPWWTP Supervisor II



Existing Collection System




OARS Tunnel Addition

OARS Tunnel


- 23,000 feet long
- 20 ft diameter
- ~180 ft deep
- Four drop shafts
- 63MG storage

OARS Dewatering Pump Station

- Tunnel must be pumped empty to be ready for next wet weather event
- 9 pumps
- 4 level sensors
- Complex control circuits



OARS Dewatering Pump Station



2 Grit Pumps

1 Mixing Pump

506

6 Dewatering Pumps

715 – Elevation picture taken from


OARS Dewatering Pumps




Dewatering Pumps

- Two pumping zones to deal with depth of tunnel
- Zone 2 – 2 pumps, 4160V, 450HP, 20MGD each
- Zone 1 – 4 pumps, 4160V, 800HP, 15MGD each
- Grit Pumps – 2 pumps, 480V, 105HP, 1MGD each
- Mixing Pump – 1 pump, 480V

Many Items in Control Circuit




Many Different Providers



Electrical sub responsible for all wires between them

Complex Control Strategy



- Each pump has an operating depth range
- Tunnel can be completely filled and flow by gravity to JPWWTP which requires throttling of gates to control the flow
- Speed of pumps must be varied with depth to maintain operation on favorable pump curve
- Many pump protective interlocks

Level Measurement Complexities



- 4 Hydrostatic level sensors
- 1 each grit sump
- 2 for dewatering pumps
 - Automatic failover
- Multiple local displays
- Must be correct to compare to other plant influent levels
- 0.25% accuracy is about ½ foot error

11885	ODS LEVEL 1	506.19 to 721.19	FT	690.83
11886	ODS LEVEL 2	506.23 to 721.23	FT	690.83
11887	OARS GRIT SUMP 1 LEVEL	501.21 to 721.21	FT	690.85
11888	OARS GRIT SUMP 2 LEVEL	501.18 to 721.18	FT	690.84


Plant Wide HMI System



Local Control Panel



Display in AFD Room



Display in AFD Room

Equipment Values

Equipment	Value
Zone 1 Pump, AFD, Rails & Brackets	~\$600,000 Each (4 total)
Zone 2 Pump, AFD, Rails & Brackets	~\$500,000 Each (2 total)
Grit Pump, AFD, Rails & Brackets	~\$170,000 Each (2 total)
Mixing Pump, Starter, Nozzles	~\$500,000

Testing must reduce risks due to equipment values.




“Press & Pray” is not a good method to manage risks

Something this complex doesn't get "turned on" one day

40 people here and no
one will stand next to the
person who hits the start
button the first time.
Why?


Answer:

*It worked the first time, they
didn't have time to walk over*



The first pump start with sewage

Testing and Validation



Process Monitoring Signals

Hydrostatic
inside
guide pipes
Grit 1

Hydrostatic
inside
guide pipes
ODS 1



Hydrostatic
inside
guide pipes
Grit 2

Hydrostatic
inside
guide pipes
ODS 2

Tested by using
smart instrument
interface to force
simulation.

Filling the tunnel
just to test level
sensors isn't
feasible


Pump Operation Simulation



Medium Voltage
Adjustable Frequency Drive


- Cannot operate pumps without sewage
- Medium voltage AFD has a motor simulation mode
- Allows for full testing of local and PLC circuits without starting the pump
- Testing without even having the pump attached was possible with a jumper to bypass the pump protection devices
- Many wiring issues fixed between the multiple vendor panels and electrical contractor. Several failed lights & indicators replaced.
- 480VAC pumps were simulated tested by removing motor leads from AFD

Tracking and Coordinating Circuit Issues



Every circuit issues was tracking individually. Microsoft Surface with OneNote was used as it could capture pictures, drawings and hold markups. Allowed for detailed notes in field with quick conversion to PDF to coordinate with Contractor, Construction Manager and Design Professional.

Simulated Tunnel Filling/Emptying



Simulated testing occurred many months before pumps were installed in shaft

AFD Simulation Mode allowed for initial testing of automatic logic against the actual control circuits.

This uncovered some additional circuit issues on pump shutdown with restart delay timer effecting the "remote" status signal to the PLC.

Pump Bump Testing

First time medium voltage applied to pumps in field



Video of each pump spinning the correct direction. Pumps tested on surface before being lowered in. Allowed for easier inspection and troubleshooting.



Special submersible cables with plug terminations. One of them was not terminated correctly. Found during bump testing and fixed.

Wet Test with Controlled Tunnel Filling


- Test each pump by doing a volume draw down test over its operating range
- Tunnel holds ~60MG
- Utilize surface sewer to fill tunnel for pump testing
- Fill tunnel during dry weather ideally
- Repeat multiple times to test each pump




*First tunnel filling test
Flow enters the dewatering pumps station*

Wet Test with Controlled Tunnel Filling

Level



Wet Test with Controlled Tunnel Filling



- Filling projections done to aid the team in responding
- Flow calculated based on the volume change in the tunnel
- Far majority of tunnel volume is in the tunnel, not in the shafts. Notice rapid rise at end as shafts are filling
- Shafts can fill in 1 to 2 hours
- One fill test was filling shafts at 1ft/min

Wet Test with Controlled Tunnel Filling

Common graphics at JPWWTP, SWWTP and SMOC to coordinate actions

OARS_TUNNEL_FILL_CALL.grf

OARS TUNNEL AND SHAFT FILLING CALL OUT ACTIONS

		CURRENT ODS LEVEL	CURRENT FDS LEVEL
CALL ACTION	CALL STATUS	ODS IS ABOVE 512.57 FT	CURRENT FDS LEVEL 689.00 FT
	CALLS NOT COMPLETE	SMOC Dispatch Action: Call crew in to operate OARS Shaft 6 gates in 2 to 3 hours to redirect flow as shafts are now filling.	
RESET CALL COMPLETION	CALLS COMPLETED	JPWWTP Action: Call plant manager and advise that the tunnel is full. Review status of FDS and WGC gates. Visually verify level at ODS.	
	CALLS NOT COMPLETE	ODS IS ABOVE 640.6 FT	LEVEL OK
	CALLS COMPLETED	SMOC Dispatch Action: Verify crew is headed toward Shaft 6. About 1 hour until first gate movement needed.	
RESET CALL COMPLETION	CALLS COMPLETED	JPWWTP Action:	
	CALLS NOT COMPLETE	ODS IS ABOVE	
	CALLS COMPLETED	SMOC Dispatch A	
RESET CALL COMPLETION	CALLS COMPLETED	JPWWTP Action:	
	CALLS NOT COMPLETE	ODS IS ABOVE	
	CALLS NOT COMPLETE	SMOC Dispatch A	
ACK CALLS COMPLETE	CALLS NOT COMPLETE	JPWWTP Action:	
	CALLS NOT COMPLETE	SWWTP Action: A	
	CALLS COMPLETED	ODS IS ABOVE	
	CALLS NOT COMPLETE	SMOC Dispatch A	
ACK CALLS COMPLETE	CALLS NOT COMPLETE	JPWWTP Action:	
	CALLS NOT COMPLETE	SWWTP Action: A	

JDO5D2_JOD5.grf

Login
Show Tags

ODS WET TES

PRINT
ALARMS
MAIN MENU
OVERVIEW
SYSTEM

LEVEL (FT)


TIME

Hist J_AB.JFDS_LIT11390C_U_USGS.F_CV
FDS LEVEL TRANSMITTER A USGS LEVEL
Hist J_AB.JODS_SEQ11884_ACTIVE_U_USGS.F
SELECTED ACTIVE ODS LEVEL USGS (F_CV)
Hist J_AB.JFDS_VLV11950_ZI_USGS.F_CV
SMR WEIR GATE POS (F_CV)
Hist S_AB.SRSP_LIT11700_U_USGS.F_CV
ICS USGS LEVEL (F_CV)

1 HR
4 HR
8 HR
1 DAY
1 WEEK SELECTED


SET CURRENT

UPSTREAM
693.38 FT




Pump Wet Testing Progressive Testing

- Pump flow rate estimated by drop in tunnel level and calculated tunnel volume
- Subsequent testing runs built on data from previous runs for each pumps baseline performance
- Due to testing of circuits before, equipment ran without control system issues.




Wet Testing Issues




- Pump 6 had a manufacturing issue that resulted in high bearing temperature shut down after several hours of operation
- Manufacturer pulled pump and repaired it
- Internal pump monitoring only way to know what is going on under 100+ feet of sewage

Wet Testing Success



All four Zone 1 pumps operation run including Pump 6.
Notice change of speed with depth

Preparing for Live Operation



- Wet testing helped establish interactions between tunnel pump station and surface sewers at JPWWTP
- Many graphic and automatic programming adjustments being made
- SOP being prepared with lessons learned from testing
- Final construction items being completed



ARCHITECTURE • ENGINEERING • PLANNING
SURVEYING • CONSTRUCTION SERVICES



Thank You to everyone who
helped with all of the testing
and issue resolutions



Will it be this nice out
when its put on-line?
Questions?

Ed Heyob

CDM Smith Automation Engineer

heyobes@cdmsmith.com

Kim Brown

JPWWTP Supervisor II

kmbrown@Columbus.gov