#### **City of Columbus**

#### **Determining WWTP Screen Capacity During Wet Weather Flows**



DEPARTMENT OF PUBLIC UTILITIES


Troy Branson, Columbus DOSD TE Dante Fiorino, Brown and Caldwell June 26, 2019



# **Screen Capacity**

- Difficult to define
- Varies depending on influent wastewater
- Recently installed two new screens
- Had to evaluate existing screens
- Want to share lessons learned


# Agenda




# **Background** Troy Branson, Columbus DOSD TE



# **Screen and Grit Building**



#### **Fine Screen Channels**



#### **Plate Screens**



### **Did You Flush This?**







# **Structural Failure**

- Plate screens experienced structural failure shortly after installation
- SWWTP developed comprehensive retrofit to prevent future failures
- Alternate operating procedure to increase screen speed, avoid blinding
- Caused excessive wear on moving parts, high maintenance cost
- Retrofits used expensive materials like titanium bolts, increasing cost



Bottom View of Screen




Side Channel View

### **Overall CEPT Project**



#### **Future Headworks Profile**


- Six new raw sewage pumps (two open slots, 4 replace)
- Two new fine screens
- New 110 MGD CEPT train after screens



Brown and Caldwell

# **Project Goals**

- Increase screen firm capacity to 440 MGD from 330 MGD
- Consider future build out capacity of 550 MGD when sizing new screens
- Meet land application regulations (5/8-inch max)
- Address existing issues



Screen Aperture Size




Screenings on Belt Conveyor

# **Existing Conditions**


Troy Branson, Columbus DOSD TE




### **Hydraulic Stress Test**



#### **Existing Screen – Previous Condition**




#### **Existing Screen – New Conditions**



# **Other Findings**

- Influent gates lower than peak level, overflowed during test
- Grit settling in influent channel in front of screen during dry weather
- Influent stop logs too difficult to close, forces operation of screens in pairs
- Effluent slide gates lower than bypass elevation, unsafe if being maintained




**Overflow Influent Gate** 



Screen Blinding (12.23.14)

# **Instrumentation Findings**

- Influent level sensors not accurate during peak flows
- Sensor set too low within channel, inundated by flow (toilet paper)
- Affects screen speed operations
- Staff unaware of bypass events
- Programmed 3 minute delay on screen speed



Influent Level Sensor

Module Properties: RACK 8.9 (1756-IF6I 1.1) General Connection Module Into Configuration Channel 0 1 2 3 4 5 Excling High Signal: Low Signat: Low Engineering: Low Engineering:	[1] Alarm Configuration [   Input Range: Sensor Offset:   Sensor Offset: Notch Filter:   Digital Filter: Digital Filter:	Calibration Backplane 0 ma to 20 ma 0.0 60 Hz 0 2 ms	
BTS: 100 - ms	Cancel	Apply	

Level Sensor Configuration

# **Design Approach**

Dante Fiorino, Brown and Caldwell




# **Capacity Analysis**

- Existing screens in future = 90 MGD
- Why was tested flow ability lower than stated capacity?
- What capacity for new screens is needed?



SGB SCADA

- 550 MGD buildout firm requires four 125 MGD
- Capacity = slot velocity x effective area (Q = vA)
- Limited by available headloss, screen blinding



Existing Screen SCADA

# **Screen Blinding**

- Effective area = Open Area Screen Blinding
- Screen blinding has significant impact on effective area
- Backing into blinding for existing screens from test leads to 40% blinding
- Same as the recommended assumption in BC guide specs



Before Test




**During Test** 


# **Slot Velocity**

- Higher slot velocity creates greater headloss
- Higher slot velocity increases blinding potential
- Creates a cycle leading to backups
- WEF MOP 8 recommends maximum v = 4 fps
- Existing screen had 7.2 fps without blinding


#### **Channel Velocity**



# **Ideal Design**



# **Realistic Design**



# **New Screens**

Dante Fiorino, Brown and Caldwell




### **Alternative Analysis**

#### **Perforated Plate Screen**



- <u>Advantages</u>
  - High capture efficiency
  - Open bid design
- Disadvantages
  - High headloss
  - Wash water demand
  - In-channel maintenance
  - Structural failure history

#### Multi-Rake Bar Screen




- <u>Advantages</u>
  - Low headloss
  - No wash water demand
  - Robust structural design
  - Open bid design
- <u>Disadvantages</u>
  - Lower capture efficiency
  - In-channel maintenance

#### Flexible Multi-Rake Bar Screen



- <u>Advantages</u>
  - Low headloss
  - Continuous removal
  - No wash water demand
  - Robust structural design
- <u>Disadvantages</u>
  - Lower capture efficiency
  - Proprietary design

#### Recommendations



# **Specification Requirements**

Don't rely on vendors to provide your screen design

- Assume 40% screen blinding minimum
- Check with hydraulic stress test on existing screens if possible
- Define Bar Loss Coefficient = 0.84
- Provide exact flow conditions and hydraulic assumptions
- Require Ohio PE structural approval of available headloss




Factory Witness Testing


### **Screen Installation**





### **Screen Installation**







#### **Screen Installation**



#### **Gate Installation**





#### **Operational Demonstration**



#### **Lessons Learned**

- Screen capacity is difficult to define
- Influent wastewater constituency impacts capacity
- Define your requirements vs. goals
  - Screen capacity, slot velocity, channel velocity, aperture size
- Be aware of design parameters, close is better than nothing
- Incorporate operational philosophy into design
- Low maintenance is key, slow and steady wins the race

# Acknowledgements

- City of Columbus
  - Darin Wise
  - Rick Kent
  - Jeff Hall
  - Stacia Eckenwiler
- Brown and Caldwell
  - Dave Nitz
  - Brett Farver

#### **Presenters**

- Troy Branson
  - Columbus DOSD TE
  - Project Manager
  - (614) 645-7423
- Dante Fiorino
  - Brown and Caldwell
  - Sr. Engineer
  - (614) 923-5009

### **Questions/Discussion**

