

# Werk & Westbourne EHRT Facility



## Startup and Commissioning Enhanced High-Rate Treatment in Cincinnati

27 June 2019

**Jim Fitzpatrick**  
Principal Process Engineer





# Agenda

- Background
- Process Overview
- Operational Modes
- Commissioning Update
- Q&A



**PROJECT GROUNDWORK**  
*your pipeline to clean water*

# Background





# Combined Sewer Overflow 522

- **Headwaters for Schaible Creek**
- **Highly active CSO**
  - 66 discharge events in typical year
  - ~600 MGY overflow
  - Wide range of flows up to 1,400-mgd
- **Site for EHRT demonstration facility**

**Community Priority to minimize public health risk, sewer debris, and odors**

# Consent Decree Requirements for EHRT

## Effluent Quality Goals (May 1 – October 30 Recreation Season)


TSS (average)	TSS <sub>INF</sub> > 150 mg/L → 70% removal, OR TSS <sub>INF</sub> ≤ 150 mg/L → ≤ 45 mg/L
<i>E. coli</i> (mean)	≥3 to 4 log reduction • Estimated to provide ≤ 1,030 cfu/mL in effluent

## Processes and Design Criteria

Fine Screens	-
Chemically Enhanced Sedimentation	SOR ≤ 7,000 gpd/ft <sup>2</sup>
Hypochlorite Disinfection	Contact time ≥ 10 minutes
Dechlorination	


# WWEHRTF Volumetric Control

- Typical Year
- Phase 1 EHRT - Pilot
- Phase 2 EHRT for  $\leq 64.7$  MG



100 Percent of Flows Receive Coarse Screenings and Floatables Control at Minimum Under Phases 1 & 2

# Process Overview



**Phase 2 EHRT Expansion**

**EHRT Basins & Outfall**

**Influent Pump Station**

**Influent Fine Screens**

**Influent Control Structure**

**Upper Muddy  
Creek Interceptor**

Westbourne Dr.


Werk Rd.





## Influent Control Structure



- Dissipate energy
- Control flows into facility up to peak capacity and release excess flows to creek
- Promote solids capture and clean-up post event for odor control
- No dry weather flow
- Coarse screening and floatables control



# ICS Screens and Floatables Control

- Flows over EHRT capacity
- 3 Bar Racks w/ 2" Openings
- 3 Flap Gates
- Overflows to Schaible Creek


Creek bed armored with ArmorFlex and aggregate infill



# Combined CFD and Physical Scale Modeling

- Optimize design of Influent Control Structure
  - Flow distribution
  - Velocity control
  - Solids deposition (grit)
  - Screen loading
- Interior baffle and wall details


Key to good design for heavy solids and post-event self-cleaning



# Influent Fine Screens

- Multi-rake bar screens
- Two @ 53-mgd each
- 5-ft wide channels
- 1/2" openings
- 75° inclination
- Direct discharge to 20 CY roll-off container





# Influent Pump Station

- Submersible, non-clog
- Two large (35-mgd), two small (18-mgd), spare slot
- Firm capacity: 71-mgd (Phase 1), 106-mgd (Phase 2)
- Level-controlled, adjustable speed
- Self-cleaning, trench wetwell

# Chemically Enhanced Sedimentation and Disinfection

- Coagulant rapid mix, polymer rapid mix and flocculation chambers
- Sedimentation: SOR 7,000 gpd/sf @ 35-mgd, 3:1 length to width
- Disinfection: 15-min contact time @ 35 mgd, 10-min @ 53-mgd
- Mixed-mode channel for disinfection of fine screened effluent (optional)



# Chemical Systems



- **Coagulant (ferric chloride)**
  - 6000-gal tank
  - Two peristaltic feed pumps
- **Polymer (anionic polyacrylamide)**
  - Two 400-gal yotes
  - Two feeder/blenders (progressive cavity pumps)
- **Sodium Hypochlorite**
  - 6000-gal tank
  - Three peristaltic hose pumps
  - Two centrifugal recirculation pumps
- **Sodium Bisulfite**
  - Two 400-gal totes
  - Two peristaltic feed pumps



# Sample System

- Three submersible sample pumps
  - Screened influent
  - CES effluent
  - Final effluent
- Pump to sample sink and refrigerated samplers





# Dewatering System

- Gravity-flow headbox
- ~50% by gravity then pumped
- Two 1.5-mgd pumps, 20 hp, submersible, non-clog
- Level-controlled, adjustable speed



# CNPW and Flushing Systems

- Break tank, 3 pumps, hydropneumatic tank
- Automated flushing sequence
  - 13 tipping buckets
  - 11 spray bars



# Operational Modes



# Pre-Event Activities

- ✓ Weather forecast
- ✓ Chemical inventories
- ✓ Weather forecast
- ✓ Exercise equipment
- ✓ Weather forecast
- ✓ Preventative maintenance

- ✓ Weather forecast
- ✓ Inspection and troubleshooting
- ✓ Weather forecast
- ✓ Training
- ✓ Weather forecast
- ✓ Public education and facility tours

**Did you check the weather forecast?**

# Treatment Modes

## Flow-Through

## First-Flush Capture

### FLOW-THROUGH MODE

$Q_{CES} \leq 35$  MGD  
 $Q_{MM} = 0$  MGD  
 $Q_{DCT} \leq 35$  MGD (CES effluent only)

Influent Control Structure, Fine Screens and Influent Pump Station

Influent Flow Splitter Box

Chemically Enhanced Sedimentation (CES) Train

Disinfection Contact Tank

Baseline

### FLOW-THROUGH MODE WITH MIXED MODE

$Q_{CES} \leq 35$  MGD  
 $Q_{MM} \leq 53$  MGD (can be concurrent with CES)  
 $Q_{DCT} \leq 88$  MGD (CES & MM effluent)

Influent Control Structure, Fine Screens and Influent Pump Station

Influent Flow Splitter Box

Chemically Enhanced Sedimentation (CES) Train

Disinfection Contact Tank

Mixed Mode Channel

Aspirational

### FIRST-FLUSH CAPTURE MODE WITH MIXED MODE

$Q_{CES} \leq 88$  MGD  
 $Q_{MM} \leq 88$  MGD  
 $Q_{DCT} \leq 88$  MGD (MM effluent only)

Influent Control Structure, Fine Screens and Influent Pump Station

Influent Flow Splitter Box

Chemically Enhanced Sedimentation (CES) Train

Disinfection Contact Tank


Mixed Mode Channel

Aspirational


Demonstration testing to compare treatment modes

# Post-Event Activities

## Dewatering




## Flushing



Coordinate with interceptor capacity and Muddy & Westbourne HRT Facility

# Commissioning Update

# Construction Progress





# Planned




# Actual



# Startup and Commissioning Plan

## GUIDE FACILITY COMMISSIONING PLAN - WERK & WESTBOURNE EHRT FACILITY

Task leads identified with underlined text





# Event Definition

## Qualifying Treatment Event

<b>Cause</b>	Wet weather causes influent flow to WWEHRTF
<b>Magnitude</b>	Influent up to at least 35 mgd
<b>Duration</b>	Release of disinfected effluent for at least 4 hours with data capture
<b>Frequency</b>	12 hours since last influent flow

**~3-MG required to yield treated effluent**

# Event Response Planning



## Weekly Testing Call

- Review weather forecast for predicted volume, intensity, and duration
- Prepare response teams
  - MSDGC (Operations)
  - Demonstration Consultant (Sampling and Testing)
  - Contractor (Construction Activities)
- Follow-up call closer to predicted event(s)



# Reliability Testing Events 1 - 6


- Over 65 hours of operation
- Hourly grab samples representing
  - 46 hours of treatment
  - 57 MG of flow
- Quantity of samples analyzed
  - 133 TSS
  - 82 *E. coli*
  - 74 residual chlorine

PARAMETER	ANALYSIS LOCATION	TYPE	FREQUENCY	INF	SINF	CES	DCT AND/OR TEFF	OUT
TSS	Laboratory	Grab	Hourly <sup>1</sup>	X	X	X <sup>2</sup>		
<i>E. coli</i>	Laboratory	Grab	Hourly <sup>1</sup>		X		X <sup>3</sup>	
Total Residual Chlorine	Field	Grab and Field Meter or Probe with Reagent	Hourly <sup>1</sup>				X <sup>4</sup>	X <sup>4</sup>
Temperature	Field	Grab (or sink) and Portable Field Meter or Probe <sup>5</sup>	Hourly <sup>1</sup>		X		X <sup>3</sup>	
pH	Field	Grab (or sink) and Portable Field Meter or Probe <sup>5</sup>	Hourly <sup>1</sup>		X		X <sup>3</sup>	
Turbidity	Field	Grab (or sink) and Portable Field Meter or Probe <sup>5</sup>	Hourly <sup>1</sup>			X <sup>2</sup>		

Notes:

1. Project Managers may elect to obtain 15-minute samples for some events when staffing and budget can

- 1.
- 2.
- 3.
- 4.
- 5.



# Testing Protocol


- Supplement Commissioning Plan
- Testing Team

Operation	Sampling and Evaluation
MSDGC	Black & Veatch
	RA Consultants
	Brown and Caldwell

- Sample up to 12 hours per event


# TSS Results

**Total Suspended Solids (TSS) - Test Event 1**




Initial ferric malfunction,  
ferric 56 mg/L & poly 0.33 mg/L

**Total Suspended Solids (TSS) - Test Event 2**




Initial ferric and polymer malfunction,  
ferric and poly overdose (pH, visual)

**Total Suspended Solids (TSS) - Test Event 3**




Facility full at startup, underfed  
ferric (22 mg/L vs. 28 mg/L)

**Total Suspended Solids (TSS) - Test Event 4**




Facility full at startup, high SOR  
53 mgd = 10,500 gpd/sf

**Total Suspended Solids (TSS) - Test Event 5**



90% TSS removal rate

**Total Suspended Solids (TSS) - Test Event 6**




CES Effluent TSS 27 mg/L

**Effluent flow-weighted TSS average  $\leq$  45 mg/L in all events**


# E. coli Results

**E. coli - Test Event 1**




SINF lab dilution inadequate, hypo feed malfunction

**E. coli - Test Event 2**




SINF lab dilution inadequate, hypo feed malfunction

**E. coli - Test Event 3**




Hypo feed malfunction during later portion of event

**E. coli - Test Event 4**




Hypo feed malfunction during later portion of event

**E. coli - Test Event 5**



3.1 log reduction; hypo feed adjusted down during later portion of event

**E. coli - Test Event 6**




3.3 log reduction; hypo feed malfunction at start

**E. Coli reduction goal met when hypo equipment functional**




# Residual Chlorine Results

Chlorine Residual - Test Event 1




Bisulfite feed malfunction

Chlorine Residual - Test Event 2




Bisulfite feed malfunction

Chlorine Residual - Test Event 3




No bisulfite feed

Chlorine Residual - Test Event 4




No bisulfite feed

Chlorine Residual - Test Event 5



Bisulfite feed malfunction


Chlorine Residual - Test Event 6



Bisulfite feed malfunction

Inconclusive. Recommend moving sample point to outfall.

# Sample Comparison (Event 5)



**Influent**



**After CES**




**Effluent**

# Lessons Learned from WVEHRTF

- Very “flashy”. Influent within ~30 minutes after ¼” rain.
- Pre- and post-event VERY important. Field adjust spray nozzles. Operator adjustable flushing program. Visual/CCTV inspection.
- Solids impact to dewatering pumps and gates
- High-rate CES and chlor/dechlor need reliable and quick-starting chemical feed
- Avoid overdosing ferric and polymer
- Is CES really needed after initial first-flush?

**SCADA invaluable for remote monitoring and readiness (chemical inventory, equipment status, etc.)**

# Acknowledgements



Definitely a team effort. Too many to list everybody here.



**Jim Fitzpatrick**

Principal Process Engineer

+1 913-458-3695

[FitzpatrickJD@bv.com](mailto:FitzpatrickJD@bv.com)



Werk & Westbourne EHRT Facility  
Ready for Test Event #1  
July 20, 2018

**THANK YOU!!!**

**Jared Hutchins**

Engineering Manager

+1 513-936-5137

[HutchinsJC@bv.com](mailto:HutchinsJC@bv.com)

**Sid Sengupta**


Project Director

+1 513-936-5121

[SenguptaS@bv.com](mailto:SenguptaS@bv.com)

# Bullpen

# Influent Characteristics



Mostly stormwater after first 2 MG

# 4 Steps to Chemically Enhanced Sedimentation (CES)

**1. Coagulant Addition.** Rapid mix. Add trivalent metal salt ( $\text{Fe}^{3+}$  or  $\text{Al}^{3+}$ )

**2. Flocculant Addition.** Rapid mix. Add anionic polymer. If Step 1 & 3 are ideal (rarely in wet weather), then optional.


**3. Flocculation.** Medium to low turbulence. Build floc and “sweep” small particles. Enhance floc settling.

**4. Settling.** Non-turbulent quiescent zone. Separate solids from liquids.

Turbulence



## Particle Conditioning




**Jar test to optimize design of Steps 1, 2 and 3**


**Steps 1, 2 and 3 are key to how fast Step 4 will work**





# Chemical Doses from CSO 522 Jar Tests (April-May 2011)



## Disinfectant




- Similar dose for hypochlorite (NaOCl) or peracetic acid (PAA)
- 4-log reduction required 7 mg/L on CES effluent, 14 mg/L on raw CSO



Further optimize during Extended Commissioning

# Influent Pump Station

- Self-Cleaning wet well




# Operational Modes

- **Flow-Through**

- Default Operational Mode
- Flow receives chemically-enhanced sedimentation
- Flow of 35 MGD is treated by CES. Flow greater than 35 MGD will be routed to Mix Mode Channel and Disinfection Contact Tank.

- **First-Flush Capture**

- Flow will be sent to CES to store as first flush capture. No chemicals to be added.
- After CES reaches a certain pre-set First-Flush Capture level, the CES weir gate will close and all remaining flow will go to Mix Mode Channel.



A screenshot of the 'HRT Facility System Control' interface. The interface includes several control panels:

- Pre-Event Control:** Includes a green 'A' button, a grey 'M' button, and a radio button for 'Pre-Event Active'.
- Treatment Control:** Includes a green 'A' button, a grey 'M' button, and a radio button for 'Treatment Active'. Below this are three buttons for flow rates: 'FLOW THROUGH' (highlighted in green), '35 MGD', '53 MGD', and '88 MGD'. A yellow box indicates 'Facility READY for DEWATERING'.
- Post-Event Control:** Includes a green 'A' button, a grey 'M' button, and a radio button for 'Post-Event Active'. Below this are radio buttons for 'Post-Event Decant Control', 'Post-Event Dewatering Control', and 'Post-Event Flushing Control'. There are also radio buttons for 'DCT Decant Enabled' and 'DCT/CES Decant Enabled'.

# Performance Criteria

CRITERIA	RT-1	RT-2	RT-3	RT-4
Influent Total Suspended Solids (ITSS) <sup>1</sup>	> 150 mg/L	> 150 mg/L	> 150 mg/L	> 150 mg/L
CES Flow Rate	35 MGD	35 MGD	53 MGD	<88 MGD
Surface Overflow Rate (SOR) <sup>2</sup>	7,000 gpd/sf	7,000 gpd/sf	10,500 gpd/sf	NA
Effluent Total Suspended Solids (ETSS) <sup>3,4</sup>	0.3 x ITSS	0.3 x ITSS	0.3 x ITSS	NA
E. coli <sup>5</sup>	3 to 4 log reduction	3 to 4 log reduction	3 to 4 log reduction	3 to 4 log reduction
Disinfection residuals <sup>6</sup>	< 1 mg/L residual chlorine	< 1 mg/L residual chlorine	< 1 mg/L residual chlorine	< 1 mg/L residual chlorine

- Notes:**
- As measured at Influent Sample location.
  - Goal is to operate at specified SOR as long as possible, and for a minimum of 15 minutes. Duration of operation at specified SOR to be confirmed in the field based on CONTRACTOR's Commissioning Plan and as agreed to by CITY and Demonstration Consultant.
  - Based on ITSS of >150 mg/L. If ITSS <150 mg/L, ETSS goal is <45 mg/L.
  - As measured at CES Effluent Sample location.
  - Removal as measured from Influent Sample location to Treated Effluent Sample location.
  - As measured at Treated Effluent Sample location.

# Test Conditions

WET WEATHER EVENT	CES FLOW RATE	TREATMENT OPERATIONAL MODE	COMMENTS
RT-1	35 MGD	Flow-Through	7,000 gpd/sf SOR, Chemical Dosage Trial No. 1A;
RT-2	35 MGD	Flow-Through	7,000 gpd/sf SOR, Chemical Dosage Trial No. 1B
RT-3	53 MGD	Flow-Through	10,500 gpd/sf SOR, Chemical Dosage Trial 2A
RT-4	<88 MGD	First Flush Capture	Mixed Mode operation required



# Reliability Test Events 1 - 6

RELIABILITY TEST EVENT	RT1	RT2	RT3	RT4	RT5	RT6
<b>Treatment Mode</b>	Flow-Through Mode (FTM) 35 MGD			FTM 53 MGD	FTM 35 MGD	
<b>Volume Treated Plus Stored (MG)</b>	4.8	6.4	12.2	13.8*	11.4	8.7
<b>Average Influent TSS (mg/L)</b>	73	35	53	31	157	35
<b>Average Effluent TSS (mg/L)</b>	42	45	25	41	16	27
<b>Influent E. coli geometric mean (MPN/100 mL)</b>	>48,392	>48,392	74,430	52,800	102,862	612,507
<b>Effluent E. coli geometric mean (MPN/100 mL)</b>	458	NA	NA	819	85	228***
<b>E. coli Reduction (Log)</b>	NA	NA	<2.0	3.0/1.8**	3.1	3.3
<b>Average Effluent Chlorine Residuals (mg/L)</b>	0.07	0.35	2.5	7.1	8.2	5.9

\* Flow/level instrument errors noted toward end of event (See Appendix A-4).

\*\* Second value includes data during periods when hypochlorite feed system was malfunctioning.

\*\*\* Conservative value; see 4.6.2 for details.